
COMPLETEPre-Cut Kit

6X8 GREENHOUSE

STORAGE SOLUTIONS



What's a posts and beam building that lets tons of light in? Our greenhouse. Fit with a combination front door, copious barn sash windows, and corrugated clear poly roofing material; these amenities allow sunlight to penetrate but do not let the building overheat.



COMPLETE PRE-CUT KIT:

A weather tight shell. The PCK is the complete kit for a design. It includes everything required to assemble the building shell and includes doors and windows.



Additional Sizes:

6X8 | 8X10 | 10X14 |

Additional Types:

FRAME ONLY KIT | COMPLETE KIT |
FULLY ASSEMBLED

Configure Yours at
WWW.JAMAICACOTTAGESHOP.COM



6X8 GREENHOUSE COMPLETE PRE-CUT KIT

Base Area: 48 sq. ft.

Total Interior Area: 48 sq. ft.

Recommended Foundation: 3–4" Crushed Gravel

Overall Dimensions: 8'6"H x 6'6""W x 8'6""D

Estimated Weight: 1900 lbs

Sill Plates

4x6 Pressure Treated Sill Plate

Walls

4"x4" Hemlock Post and Beam Wall Framing

Wall Height: 74"

Siding: 1" rough sawn Pine Board & Batten

1" rough sawn Pine Corner, Door, Window & Fascia Trim

Roof

Gable Roof Style Roof Pitch: 6/12 2"x4" rough sawn Hemlock Rafters 24" On Center The complete pre-cut kit includes a treated sill plate and hemlock framing, pine board and batten siding, clearpoly roof, combo screen door and barn sash windows. Note: Pictures may reflect client upgrades and modifications that do not come standard.

1"x6" rough sawn Hemlock Exposed Collar Ties

1"x4" rough sawn Hemlock Strapping 20" On Center

Corrugated Clear Poly Roofing w/ Galvanized Ridge Cap

Door & Windows:

Door: 1 (qty) 2-8 x 6-0 Combination Screen/Glass Door

Windows: 4 (qty) 3'x2' eightlite Hinged Barn Sash Window, 1 (qty) 4'x2' ten-lite Hinged Barn Sash Window

Additional Features

16" rough sawn Pine Workbench Around Interior

Assembly & Logistics Information

Estimated Assembly Time: Two People: 14 hrs

Estimated Shipping Cube Sizes

Cube 1: 42"x44"x96"

GRNH.6X8.PCK