STORAGE

SOLUTIONS

FULLY ASSEMBLED



What's a posts and beam building that lets tons of light in? Our greenhouse. Fit with a combination front door, copious barn sash windows, and corrugated clear poly roofing material; these amenities allow sunlight to penetrate but do not let the building overheat.



FULLY ASSEMBLED:

A weather tight shell. Specifications are the same as a PCK. Fully assembled prefabricated sheds and cottage buildings deliver exclusively to the northeast USA.



Additional Sizes: 6X8 | 8X10 | 10X14 |

Additional Types:

FRAME ONLY KIT | COMPLETE KIT |
FULLY ASSEMBLED

Configure Yours at
WWW.JAMAICACOTTAGESHOP.COM

8X10 GREENHOUSE



8X10 GREENHOUSE FULLY ASSEMBLED

Base Area: 80 sq. ft.

Total Interior Area: 80 sq. ft.

Recommended Foundation: 6–8" Crushed Gravel

Overall Dimensions: 8'6"H

x 8'6"W x 10'6"D

Estimated Weight: 4400 lbs

Sill Plates

4x6 Pressure Treated Sill Plate

Walls

4"x4" Hemlock Post and Beam Wall Framing

Wall Height: 66"

Siding: 1" rough sawn Pine Board & Batten

1" rough sawn Pine Corner, Door, Window & Fascia Trim

Roof

Gable Roof Style Roof Pitch: 6/12

2"x4" rough sawn Hemlock Rafters 24" On Center The fully assembled unit includes a treated sill plate and hemlock framing, pine board and batten siding, clearpoly roof, combo door and windows. Note: Pictures may reflect client upgrades and modifications that do not come standard.

1"x6" rough sawn Hemlock Exposed Collar Ties

1"x4" rough sawn Hemlock Strapping 20" On Center

Corrugated Clear Poly Roofing w/ Galvanized Ridge Cap

Door & Windows:

Door: 1 (qty) 2-8 x 6-0 Combination Screen/Glass Door

Windows: 2 (qty) 3'x2' eight-lite Hinged Barn Sash Window, 4 (qty) 4'x2' ten-lite Hinged Barn Sash Window, 3 (qty) 16"x21" fourlite Fixed Barn Sash Windows

Additional Features

24" rough sawn Pine Workbench Around Interior

Delivery & Logistics Information

Fully Assembled prefabricated sheds and cottage buildings are deliverable exclusively to the Northeast USA.

GRNH.8X10.FA