STORAGE SOLUTIONS

# COMPLETE Pre-Cut Kit

Sturdy, attractive, and practical, this rugged Vermont-made post and beam shed does it all to meet your firewood and equipment storage needs while also shedding snow off the rear to allow for easy year-round access.



#### **COMPLETE PRE-CUT KIT:**

A weather tight shell. The PCK is the complete kit for a design. It includes everything required to assemble the building shell and includes doors and windows.



Step-by-Step Instructions
 All Fastening Hardware Include

#### Additional Sizes:

4X8 | 4X10 | 4X12 | 6X12 | 6X14 | 6X16 | 8X14 | 8X16 | 8X20 | 10X16 | 10X20 | 12X20 |

Additional Types: FRAME ONLY KIT | COMPLETE KIT FULLY ASSEMBLED |

Configure Yours at
WWW.JAMAICACOTTAGESHOP.COM

### **8X16 WEEKENDER**



#### 8X16 WEEKENDER COM-PLETE PRE-CUT KIT

Base Area: 128 sq. ft. 8x6 Enclosed Storage Space: 48 sq. ft. 8x10 Woodbin: 80 sq. ft. Recommended Foundation: Compacted 12" Crushed Gravel Overall Dimensions: 10'6"H x 17'2"W x 9'6"D Estimated Weight: 4300 lbs

#### Floor System

2 (qty) 6x6x16' Hemlock Skids 2"x6" rough sawn Hemlock Joists 16" On Center 34" CDX Plywood Enclosed Storage Side Floor Decking 1" rough sawn Hemlock Woodbin Side Floor Decking Floor Weight Rating: 210 lbs / sq.ft.

#### Walls

4"x4" Hemlock Post and Beam Wall Framing Wall Height: Front: 83 Rear: 71 8' Full Partition Siding: 1" rough sawn Pine Board & Battens 1" rough sawn Pine Board On Woodbin Side 1" rough sawn Pine Corner & Door Trim & 2" rough sawn Pine Fascia & Shadow Trim The complete pre-cut kit includes hemlock framing, pine board and batten siding, floor decking, corrugated metal roof and a double pine door. Note: Pictures may reflect client upgrades and modifications that do not come standard.

#### Roof

Saltbox Roof Style
Roof Pitch: Front: 12/12 Rear: 6/12
2"x6" rough sawn Hemlock
Rafters 24" On Center
1"x6" rough sawn Hemlock
Exposed Collar Ties
1"x4" rough sawn Hemlock
Strapping 20" On Center
Corrugated 29g Metal
Roofing, Color: Evergreen

#### Doors & Rough Opening:

1 (qty) 5-0 JCS-built 2"Thick rough sawn Pine Double Doors w/ 3x5 Pressure Treated Ramp, 1 (qty) 98"W x 73" H Rough Opening

#### Additional Features

Holds 4.1 Cords

## Assembly & Logistics Information

Estimated Assembly Time: Two People: 22 hrs Estimated Shipping Cube Sizes Cube 1: 42"x48"x192"

WKND.8X16.PCK

©2021 Jamaica Cottage Shop, Inc. • 1-802-210-1249 • www.JamaicaCottageShop.com